

## REQUIRED INSPECTIONS

### REQUESTS MUST BE MADE 24 HOURS IN ADVANCE OF INSPECTION

- **FOOTINGS** – After excavation & properly prepared for concrete but prior to pouring.
- **CONCRETE SLABS** - After properly prepared for concrete but prior to pouring.
- **POST HOLES** – After holes are dug.
- **FRAMING** – After framing is complete with any associated rough wiring, rough plumbing or mechanical work is installed but prior to insulation. (Do not cover porches) \*Rough plumbing MUST be approved by the Health Dept prior to inspection.
- **ROUGH ELECTRIC** – Normally done at the same time as framing inspection or if framing inspection is not required, after all wiring is installed but prior to covering – Grounds to be mechanically fastened (wire nut or crimp)
- **ROUGH HEATING & COOLING** – Normally done at the same time as framing inspection or if framing inspection is not required, after all ductwork, flue's or associated work is properly installed & prior to covering. Any in slab ductwork will be inspected at concrete slab inspection.
- **INSULATION** – After all insulation is installed but prior to drywall.
- **NEW ELECTRIC SERVICE** – After meter socket has been mounted, wired to main service disconnect & properly prepared for connection to power company. This inspection can be done at rough electric inspection or done separately.
- **ELECTRIC SERVICE UPGRADE, REPAIR OR REPLACEMENT** – After service has been upgraded, repaired or replaced & properly prepared for connection to power company. All existing circuits tied back in & identified. Any new circuits will be inspected at this time.
- **TEMPORARY ELECTRIC SERVICES ON POLES OR OTHERWISE** – After service has been constructed & properly prepared for connection to power company.
- **MASONRY FIREPLACE OR MASONRY CHIMNEYS** – Normally 3 inspections – One for footing – One when first flue liner is set – One prior to closing chimney top.
- **PRE-FABRICATED FIREPLACE OR HEATING STOVE** – Normally 2 inspections – One after flue is installed & is accessible. One when unit is complete & properly installed for use.
- **ABOVE GROUND SWIMMING POOLS** – Normally 1 inspection after pool is complete & properly wired for use.
- **IN GROUND SWIMMING POOLS** – Normally 3 inspections. One for lower bonding & underground conduits. One for upper bonding. One for final inspection after pool is complete & properly wired for use.
- **FINAL ELECTRIC** – After all electrical work is complete & properly working. Done at same time as final structure.
- **FINAL HEATING & COOLING** – After all units are complete & in proper operation. Done at the same time as final structure.
- **FINAL STRUCTURE** – Prior to occupancy & if applicable after all associated final electrical, final mechanical & final plumbing work has been approved. Final plumbing MUST be approved by the Health Dept prior to inspection.